



DEPLOYED LOGIX
SHELTERS
THE FIRST IN THE FIELD

ASAP-HUB® // US PATENT: 11280107 // OTHER PATENTS PENDING

- **INTERCHANGEABLE CONNECTIVITY.**
- **THE CENTER OF YOUR SHELTER COMPLEX.**
- **WITHSTANDS THE HARSHTEST CONDITIONS.**
- **CAN STAND ON ITS OWN.**

At Deployed Logix we're redefining rapid deployment. Through our extensive work with law enforcement, search and rescue teams, various first responders, private organizations both domestically and abroad, and the military, our team understands that when a crisis calls, seconds count. Discover why we are the leader in American-made, rapidly deployable disaster preparedness products.

Specification and design may be altered without notice due to continuous product development. LAST UPDATED MAY 2022.

Proudly made in the USA.
CAGE CODE: 7CFK2 I DUNS#: 079751064



ASAP-HUB® SPECIFICATIONS			
TIME UNDER CANOPY:	15 minutes w/ four personnel		
TOTAL SETUP TIME:	25 minutes w/ four personnel		
SHELTER AREA:	17 x 17 ft (5.18 x 5.18 m) // 289 ft² (26.85 m²)		
WIND LOAD:	65 MPH, gusts 75 MPH (105 kmh/gusts 121 kmh)		
SNOW LOAD:	10 lb/ft² (4.54 kg/m²)		
VINYL:	Mil-spec blackout, NFPA approved flame and mold resistant		
DIMENSIONS:			
Footprint (length x width): 17 x 17 ft (5.18 x 5.18 m)			
Peak: 9.50 ft (2.90 m)			
Square footage: 289 ft² (26.85 m²)			
Maximum dimensions needed for deployment: 20 x 20 x 10 ft (6.10 x 6.10 x 3.05 m)			
PACKAGED DIMENSIONS AND WEIGHTS:			
Frame Bag 1: 80 x 11 x 11 in (203.20 x 27.94 x 27.94 cm) Weight: 100 lb (45.4 kg)			
Frame Bag 2: 80 x 11 x 11 in (203.20 x 27.94 x 27.94 cm) Weight: 95 lb (43.1 kg)			
Frame Bag(s) 3, Vinyl Components: 34 x 25 x 20 in (86.36 x 63.50 x 50.80 cm) Weight: 150 lb (68.0 kg)			
PACKAGED DIMENSIONS IN THE BEST CASE BY DLX™:			
Hard Case 1: 101.13 x 25 x 24 in (256.87 x 63.50 x 60.96 cm)			
Hard Case 2: 50.13 x 25 x 24 in (127.33 x 63.50 x 60.96 cm)			
WEIGHTS:			
Roof: 45 lb (20.4 kg)			
Endwalls: 55 lb (24.9 kg)			
Floor: 30 lb (13.6 kg)			
Stake Kit: 20 lb (9.1 kg)			
Frame Arches: 105 lb (47.6 kg)			
Frame Legs and Roof: 90 lb (40.8 kg)			
ASAP-HUB® STANDARD COMPONENTS BY PACKAGE			
KIT INCLUDES	SAHUB	SCAHUB	SMRPAHUB
FRAME (1)	x	x	x
ROOF (1)	x	x	x
ENDWALLS (4)	x	x	x
FLOOR (1)	x	x	x
STAKE KIT (1)	x	x	x
REPAIR KIT (1)	x	x	x
BEST CASE BY DLX™ (1)		x	x
TABLE KIT (1)		x	x
INSULATION LINER (1)			x
ATLAS® ANCHOR (4)			x
STRING LIGHTS (1)			x
WIRING HARNESS (1)			x
TOTAL WEIGHT:	415 lb (188.2 kg)	535 lb (242.7 kg)	714 lb (323.9 kg)